



PROPOSITION # P23069

DATE : March 13th 2024

CLIENT : **MOISHE FRIEDMAN**
6529 Hutchison Street
Montreal, QC H2V 4H9

CONTACT : **Moishe Friedman**

REFERENCE : **BETH ESTHER ACADEMY**
Control

Sir,

We are pleased to present to you our proposal for the control of the ventilation & air conditioning work to be carried out in reference to the project mentioned above.

DESCRIPTION OF WORK (supply and installation):

1. Chiller & Unit control :

1.1. 1x WEB-S-1-N4 Supervisor with 1 Niagara network connection c/w 5 years maintenance;

NOTE : **Not included:** - Computer or virtual computer on your server
- IT labor for local and/or external IP address
- Labor for maintenance.

1.2. 1x WEB-8000 controller with 10 device Core 500 points and 5 years software maintenance;

NOTE : **Not included** - Labor for maintenance.

1.3. 3x PUB6438SR/U Spyder controller 6UI, 4DI, 3AO, 8 24VAC 1.5A relay output for boiler, air units;

1.4. 2x SIO6042 Spyder extensions 6UI 4AO 2DO;

1.5. 2x TR71/U Zio LCD/sylk bus wall module thermostat.

1.6. 4x TR40 wall module sensor, temperature, sylk-bus;

1.7. 2x G780+2*AFX24-MFT-X1 Globe Valve (GV), 3", 3-way, ANSI Class (for each air unit coil cooling);

NOTE : **Will be install by plumber**

1.8. 2x NFB24-SR Damper Actuator, 90 in-lb [10 Nm], Spring for valve;



2. General Items :

- 2.1. Low voltage wiring of controls in control panels only
- 2.2. Setting up the devices.
- 2.3. Refrigeration and control labor.
- 2.4. Start-up and one (1) year warranty (parts and labor)
- 2.5. Day jobs.

BUDGET PRICE : \$ +/- 44 750.00 Dollars, tps et tvq en sus.

PRICE VALID FOR 30 JOURS

This control system is the same as Marvid Poultry

Not Included :

- A) All electrical work (circuits, starters, fuseless disconnectors and connections to devices).
- B) **EMT conduit and off-panel wiring.**
- C) Connection to the fire alarm system.
- D) 20H bank Hour for one year distance

We appreciate your consideration for this submission. Hoping everything meets your expectations, do not hesitate to contact us for further information.

Acceptance of the quote by the client

PO #: _____

Total Amount : _____

Client signature

Name in block letters

Date

Julien Collette
 Projet manager, designer HVAC
julien.collette@synairtech.ca